

HIPPODROME



INSTALLATION AND SERVICE MANUAL

for

UPRIGHT GAME

and

CONVERSION KIT

DATA EAST USA, INC.

470 Needles Dr.

San Jose, CA 95112

FCC WARNING

This equipment generates and uses radio frequency energy and if not installed and used properly, i.e; in strict accordance with this instructions manual, may cause harmful interference to radio communications. This equipment has been tested and found to comply with the limits for a Class A computing device pursuant to Subpart J of Part 15 of the FCC rules, which are designed to provide reasonable protection against such interference when the equipment is operated in a commercial environment.

Operation of this equipment in a residential environment is likely to cause interference in which case the user, at his own expense, will be required to take whatever measures are necessary to correct the interference.

FBI WARNING

Federal law provides severe civil and criminal penalties for the unauthorized reproduction, distribution, or exhibition of copyrighted audio-visual works and video games. The Federal Bureau of Investigation investigates allegations of criminal copyright infringement.

COPYRIGHT NOTICE

HIPPODROME™ is Copyright 1988 Data East Corporation, sold exclusively in the United States of America and Canada by Data East USA, Inc. All rights reserved.

ENVIRONMENTAL DATA

This product is intended for indoor use only, power requirements are 105-125 volts AC, 50-60 hz, and requires a 3 wire grounded outlet.

SERVICE PROCEDURES

To obtain replacement parts and technical service, contact the authorized Data East Distributor in your area. If you require referral or further technical assistance, you may contact Data East's Customer Service department during the hours of 8:00 am to 5:00 pm Pacific Time at (408) 286-7074.

AAMA WARNING

DATA EAST USA, INC., in cooperation with the American Amusement Machine Association, has installed an "AAMA PROTECT" certification label on each HIPPODROME PCB manufactured for legal sale in the United States of America.

If you are offered a HIPPODROME PCB that does not have the "AAMA PROTECT" certification label, you should suspect that the board is not legal, and should contact DATA EAST USA, INC., at (408) 286-7074, or Bob Fay of the AAMA at (703) 548-8044.

HIPPODROME™

UPRIGHT GAME and CONVERSION KIT

Table of Contents

1.	UPRIGHT GAME	
	A. Installation and Setup.....	1
	B. System Adjustments.....	2
	C. Replacement Parts Lists.....	3
2.	CONVERSION KIT	
	A. Specific Requirements.....	5
	B. Replacement Parts List.....	5
	C. Installation Instructions.....	6
3.	GAME INFORMATION	
	A. Game Options.....	10
	B. PCB Edge Connector Pin-outs.....	11
4.	SCHEMATIC DIAGRAMS	
	A. DE 0318-3 Program Board.....	14
	B. DE 0297-3 Main Board.....	31
5.	CUSTOMER REPLY FORM.....	49
6.	WARRANTY INFORMATION..	Inside Back Cover

© 1989 DATA EAST USA, INC.
470 Needles Dr.
San Jose, CA 95112

HIPPODROME™

UPRIGHT GAME

1. A. INSTALLATION AND SET UP

Thank you for buying a DATA EAST product. We are sure that you will enjoy many years of profitable and entertaining operation with your HIPPODROME™ game.

Your game was thoroughly tested, 'burned-in' and inspected before it was shipped. However, it may have been subjected to some rough handling, or a rough ride in a truck, since it left our factory, so please follow the steps listed below before attempting to operate the game.

Locate the door keys supplied and remove the Rear Access Door.

Check the Main Harness for loose or unplugged connectors, and check for secure mounting of the monitor, power supply, and game pcb. Stabilize the cabinet using the leg levelers in the floor of the cabinet to prevent the game from rocking.

The selectable options have been pre-set at the factory for optimum player appeal. However, to set the game up for your specific requirements, refer to the operator selectable options on Page 10 in Chapter 3, Section A of this manual.

Remove the power cord from the inside of the cabinet and insert the strain relief plate into the slot at the bottom of the rear access door opening. Plug the AC cord into a grounded 117 VAC outlet and flip the power switch to the ON position. Allow 2 to 3 minutes for the monitor to warm up and check for proper demonstration mode video on the screen. Insert the proper coinage into a coin slot and start a game. Check for proper operation of all joystick controls and switches.

HIPPODROME™

UPRIGHT GAME

1. B. SYSTEM ADJUSTMENTS

The Volume Control, Coin Counter, and Service Switch are located on the Service Panel. The Service Panel is located inside the Coin Door, mounted on the wall of the cabinet on the left side.

The Coin Counter increments once for every coin dropped through either coin entry slot.

HIPPODROME™ utilizes monophonic sound. A single Volume Control is used to adjust the overall loudness of the game sounds. NOTE: The volume control potentiometer on the Main PC Board is pre-set to mid-range at the factory and should not be adjusted.

The Service Switch can be used to add credits to the game without incrementing the Coin Counter.

The fuses for the AC power line and the 12 volt Supply are located on the Power Supply assembly. The fuse holders are labeled as to the proper fuse ratings. The line fuse should be 3 A slow blow, and the 12 volt fuse (used for coin door lamp circuit) should be 1 A fast blow.

The +5 vdc adjustment level control on the Power Supply's Switching Regulator is pre-set at the factory. In the event that an adjustment is required, measure the +5 volt level present at the game logic pcb with a Digital Multi-Meter while adjusting the output level of the Switching Regulator. The voltage must measure between +4.90 vdc to 5.10 vdc at the game logic pcb for proper operation.

**WARNING: DANGEROUS VOLTAGE LEVELS ARE PRESENT IN
AND AROUND THE MONITOR AND POWER SUPPLY ASSEMBLY.
ADJUSTMENTS AND REPAIRS SHOULD BE ATTEMPTED ONLY
BY QUALIFIED ELECTRONIC TECHNICIANS.**

HIPPODROME™

UPRIGHT GAME

1. C. REPLACEMENT PARTS LISTS

The following lists indicate the major replaceable parts for your HIPPODROME™ Upright Game, Control Panel Assembly, Service Panel Assembly and Power Supply Assembly. When ordering replacement parts, please be sure to provide both the complete description and part number.

P/N 500-0039-00 Upright Game

<u>Part Number</u>	<u>Description</u>	<u>Remarks</u>
031-0005-00	Speaker, 5" deluxe	
365-0013-00	Cabinet Assy, 1US34-style	gray (45 deg)
380-0002-00	Bezel, Monitor, black	
510-0002-03	Power Supply Assy	5v-11a, 12v-1a
510-0004-00	Coin Door Assy, 2 slot	
510-0065-00	Monitor, Universal H/V	
510-0151-00	PCB Set, Hippodrome	
510-0155-00	Control Panel Assy, Hippodrome	
515-0029-02	Panel Assy, Service	
535-0078-00	Retainer, Plex, Marquee	
660-0001-01	Plex, Clear, 23.75 X 23.75	
660-0001-07	Plex, Clear, 26.06 X 7.6 X .125	(for marquee)
780-0129-00	Manual, Service & Operation, Hippodrome	
810-0040-00	Underlay, Monitor, Hippodrome	
820-0040-00	Decal, Side, Generic 5.13.87	Blue
830-0045-00	Overlay, Marquee, Hippodrome	(for marquee plex)

HIPPODROME™
UPRIGHT GAME

1. C. REPLACEMENT PARTS LISTS (continued)

P/N 510-0155-00 Control Panel Assembly

<u>Part Number</u>	<u>Description</u>
180-0024-00	Pushbutton Assy, w/microswitch, Black
180-0024-02	Pushbutton Assy, w/microswitch, Red
180-0024-04	Pushbutton Assy, w/microswitch, Yellow
406-0180-02	Tag, Pushbutton ID, "2 Players"
406-0180-05	Tag, Pushbutton ID "1 Player" (upside down)
406-0180-07	Tag, Pushbutton ID, "Jump"
406-0180-16	Tag, Pushbutton ID, "Attack"
450-0014-01	Joystick, Happ Ctrl, 8 way, w/Microswitches
535-0061-00	Control Panel, Bare
800-0030-00	Overlay, Control Panel, Generic, Blue

P/N 515-0029-02 SERVICE PANEL ASSEMBLY

<u>Part Number</u>	<u>Description</u>	<u>Comments</u>
090-0002-00	Coin Counter, 12 volt	w/internal diode
123-0008-11	Potentiometer, 100 Ω, 4 watt	Volume Control
180-0024-xx	Pushbutton Assy, w/Micro switch	(any color will do)
535-0084-00	Bracket, Service Panel	

P/N 510-0002-03 POWER SUPPLY ASSEMBLY

<u>Part Number</u>	<u>Description</u>	<u>Comments</u>
001-0012-00	Switching Regulator	+5 V @ 11A, 12V @ 2A
010-0001-00	Transformer, Isolation	1 A (min) @ 115 VAC
150-0006-00	Filter, Noise	Delta # 10DKAG5
200-0002-00	Fuse, 1 A Fast Blow	for Coin Door Lamps
200-0011-00	Fuse, 3 A Slo Blow	115 VAC Line Fuse
515-0002-01	Power Cord Assy	w/strain relief plate
660-0003-00	Fish Paper	(safety cover)

HIPPODROME™ CONVERSION KIT

2. A. SPECIFIC REQUIREMENTS

Thank you for purchasing a DATA EAST game. We hope that it will give you many years of productive enjoyment. Your HIPPODROME™ game conversion kit is intended to be installed into an existing video game cabinet, and comes with all the necessary components to make the converted unit look and play like a new, dedicated game.

THE GAME TO BE CONVERTED MUST MEET THE FOLLOWING REQUIREMENTS

MONITOR: Horizontal, RGB, Negative Composit Sync Input

POWER SUPPLY: + 5VDC @ 10 amp, +12VDC @ 1 amp

2. B. REPLACEMENT PARTS LIST

The following items are provided with your HIPPODROME™ generic kit. When ordering replacement parts, please be sure to provide the complete description and part number.

Part Number	Description	Remarks
036-0158-02	Hrns, JAMMA - GENERIC KIT	
180-0024-00	Pushbutton Assy, w/microsw, Black	
180-0024-02	Pushbutton Assy, w/microsw, Red	
180-0024-04	Pushbutton Assy, w/microsw, Yellow,	
406-0003-00	Label, FCC Warning	
406-0085-00	Label Set, Pushbutton ID	
450-0014-01	Joystick, w/Microswitches	Happ Contrls
510-0151-00	PCB set, Hippodrome	
660-0001-00	Plex, Clear, 23.75 X 7.6	(for control panel)
660-0001-02	Plex, Clear, 24 X 9 X .125	(for marquee)
780-0129-00	Manual, Inst., Hippodrome	
800-0030-00	Overlay, Ctrl Pnl, Generic	blue DATA EAST
810-0040-00	Underlay, Mon. Hippodrome	
820-0040-00	Decal, Side, Generic	blue DATA EAST
830-0045-00	Overlay, Maquee, Hippodrome	

HIPPODROME™

CONVERSION KIT

2. C. INSTALLATION INSTRUCTIONS

When selecting a game to convert, make sure that the Power Supply, the Monitor, and the Coin Acceptors are functional. There is nothing more frustrating than installing a conversion kit and having it not operate due to a faulty monitor or power supply. You should not expect the new logic PCB to be defective. It has been thoroughly tested and 'burned-in' at the factory.

It is mandatory that the cabinet be wired to conform with all National and Local electric codes before the conversion is attempted. The primary power input section must have adequate noise filtering on the AC line to prevent undesirable conducted radio frequency interference (RFI). "Adequate" is defined as a filter with both common mode and differential mode filtering and a minimum current capacity of 2.5 Amp.

The Federal Communications Commission (FCC), and other regulatory agencies, require that every video game be clearly labeled with the Name and Address of the Original Manufacturer, Date of Manufacture (or Serial Number), Power requirements, Suitability for indoor or outdoor use, and the Model number of the unit. **DO NOT DESTROY OR DEFACE THE ORIGINAL GAME ID TAG.** In addition, the FCC requires that, after conversion, the unit must be labeled with a suitable warning stating that radio frequency interference may result from use in a residential area. An acceptable label is included with this kit.

**IT IS THE RESPONSIBILITY OF THE PERSON INSTALLING
THIS KIT TO COMPLY WITH ALL LABELING REQUIREMENTS!**

2. C. 1. TAKING IT APART

Performing a few simple tasks when preparing a game to be converted can save you much time and effort when you are installing the conversion kit.

Find the Wiring Diagram of the game to be converted. You will need to identify the required DC power supply output wires and the monitor video and sync wires. Note the color coding of these wires, or better yet, label them as to their function. This kit contains a new Main Harness, but you will need to splice it into the existing power supply and video wiring.

Remove the existing game harness parts that will not be used in this conversion. **NOTE:** You are modifying only the secondary (DC from power supply) and I/O (video, speaker, and controls) sections of the wiring. **DO NOT MODIFY OR REMOVE THE PRIMARY AC WIRING.** The original manufacturer should have designed and built it to comply with Local and National Electrical Codes and FCC regulations. It must not be altered.

HIPPODROME™

CONVERSION KIT

2. C. 1. *TAKING IT APART (continued)*


Remove the original game pcb from the cabinet. Remove all exterior decals, and repair any cabinet damage. Repaint the cabinet if necessary. Remove the monitor plex (or glass). If your plex has silkscreened art work on it, you will need to strip it off, or replace it with a new piece cut to the same size. Using the old Monitor Plex as a template, cut the Monitor Underlay card, supplied with this kit, to the same size as the old plex. NOTE: Be certain that the opening in the Underlay Card lines up with the monitor screen.

Remove the Marquee Plex from the game and use it as a template to cut the new Marquee Plex down to the correct size. Remove the control panel from the game and remove all controls and graphics from it. Drill and/or punch any required new holes for the control panel. HIPPODROME™ is an interactive, two player game (player vs. player, or player vs. computer), and requires two joy sticks. Each player also requires a minimum of two "shoot" buttons, although four are recommended (to allow either player to 'shoot' either left handed or right handed). See the diagram below for a suggested control panel layout. If you are going to cover the control panel with clear plex, you should carefully cut it to fit the control panel at this time. Thoroughly clean the control panel so that the new control panel overlay will adhere to it aggressively.

2. C. 2. *PUTTING IT TOGETHER*

Install the Control Panel Overlay by peeling off the paper backing and carefully laying the overlay down on the panel. Smooth it out starting in the center and working your way out to the edges, removing all of the trapped air pockets. If possible, cut the edges of the overlay oversize and fold the excess under the panel. Cut out the button and joy stick holes. Install the BUTTON ID labels supplied with the kit.

FIGURE 1 - Suggested Control Panel Layout



HIPPODROME™

CONVERSION KIT

2. C. 2 *PUTTING IT TOGETHER (continued)*

You may wish to cover the control panel overlay and button ID labels with clear plex at this time. Install the new buttons and joy stick at this time. Refer to Figure 1 on the previous page for recommended control layout.

GAME PCB: Mount the Game PCB in a convenient location in the cabinet, using the mounting feet and hardware supplied with the pcb.

MAIN HARNESS: The generic, main harness provided with this kit has a standard, 56 pin JAMMA connector. All required RFI filtering is incorporated on the PC Board. No external filtering is required. The Game pcb has a 56 pin, JAMMA connector. Refer to Figure 2, on page 11 for information pertaining to signals and functions as they are found on the game pcb edge connector.

POWER SUPPLY WIRING: Separate the DC power wires and route them through the cabinet to the Power Supply. Try to keep the length of these wires to a minimum for best results.

NOTE: USE A MINIMUM OF TWO (2) WIRES EACH FOR THE +5 VOLTS AND THE GROUND LINES BETWEEN THE POWER SUPPLY AND THE PCB. Terminate these wires at the power supply as required.

NOTE: IMPROPER WIRING WILL DAMAGE THE PCB SET AND VOID THE WARRANTY!

PLAYER CONTROL WIRING: Route the push button and joy stick wires up to their proper destinations, cut to length, and terminate as required.

MONITOR WIRING: The game outputs are Positive for the Red, Green and Blue signals, and Negative Composite Sync. If your monitor has separate Horizontal and Vertical sync inputs, hook the Composite sync to the negative Horizontal input. This method will work on most monitors. However, some Electrohome models require that the Composite sync signal be hooked up to both the negative Horizontal and Vertical inputs. Contact your distributor for more information if you are uncertain as to how to hook up the monitor wires.

COIN DOOR: The coin counter(s) may be the 12 volt or the 6 volt type, as the game pcb utilizes an open collector drive circuit. Hook one coin counter wire to the required, positive voltage and the other wire to the coin counter signal wire from the main harness edge connector. Refer to the standard connection diagrams on page 12.

HIPPODROME™

CONVERSION KIT

2. C. 2. *PUTTING IT TOGETHER (continued)*

GRAPHICS: The monitor underlay card is pre-printed with game instructions. Install the underlay card under a clean, clear plex or glass. Check any marquee lamps for proper operation. Replace any burned out lamps. The HIPPODROME™ marquee overlay must be installed on a piece of clear plex. Before you do that, use the old plex as a guide for cutting the 24 x 9" clear plex (provided with this kit) to the proper size. Next, remove the protective coverings from the clear plex, and carefully clean it with a good, anti-static cleaner to remove any and all specks of dust, etc, that may have been attracted to it. Then remove the paper backing from the marquee overlay, and affix it to the clear marquee plex. Make sure that the copyright notice will not be hidden by any plex retainers when installed. Smooth out any and all bubbles. Install the two DATA EAST side decals.

IMPORTANT! Install the "FCC Warning" label to the upper rear of the cabinet.

THE BIG TEST!

Remove the Main Harness connector from the game pcb. Apply power. Measure the +5 volts at the edge connector of Main Harness (at the point where it would connect to the game pcb). Adjust to +5.15 VDC using a Digital volt meter. Measure the +12 volts and the -5 volts (if any) to ensure that they are connected properly and are on the correct terminals. **TURN THE POWER OFF!** Now reconnect the Main Harness connector to the game pcb, and apply power once again. The attract mode video should appear on the screen. Adjust the picture size and colors on the monitor to get the optimum appearance. Adjust the Sync and Hold controls on the monitor for a stable picture. Coin it up and give it a try! Test all the controls and check the sound for proper operation.

CONGRATULATIONS! You have successfully installed your DATA EAST conversion kit. We hope that it gives you many years of successful operation.

HIPPODROME™

UPRIGHT GAME & CONVERSION KIT

3. A. OPERATOR SELECTABLE OPTIONS

The HIPPODROME™ game allows for operator adjustable pricing, number of lives, difficulty, etc. These are accessed by the two 8 position dipswitches located on the main logic pcb. Tables 1 and 2 outline the available options.

TABLE 1 - Dipswitch 1

		1	2	3	4	5	6	7	8
Game Charge (Right) COIN 1	1 coin = 1 credit	OFF	OFF						
	1 coin = 2 credit	ON	OFF			A			A
	2 coin = 1 credit	OFF	ON			L			L
	3 coin = 1 credit	ON	ON			W			W
Game Charge (Left) COIN 2	1 coin = 1 credit			OFF	OFF	Y			Y
	1 coin = 2 credit			ON	OFF	S			S
	2 coin = 1 credit			OFF	ON				
	3 coin = 1 credit			ON	ON	O			O
Attract Mode	Yes:					F	OFF		F
	No:						ON		
Flip Screen?	Normal:							OFF	
								ON	

TABLE 2 - Dipswitch 2

		1	2	3	4	5	6	7	8
Number of lives	2 Lives:	OFF	OFF						
	3 Lives:	ON	OFF						
	1 Life:	OFF	ON						A
	5 Lives:	ON	ON						L
Game Difficulty	NORMAL:			OFF	OFF				A
	EASY:			ON	OFF				Y
	HARD:			OFF	ON				S
	HARDEST:			ON	ON				
Power Level (player & enemy)	MEDIUM:					OFF	OFF		O
	LOW:					ON	OFF		F
	VERY LOW:					OFF	ON		
	HIGH:					ON	ON		
Enemies Power Decrease when game is continued	2 dots:							OFF	
	3 dots:							ON	

HIPPODROME™
UPRIGHT GAME & CONVERSION KIT

3. B. PCB EDGE CONNECTOR PIN-OUTS

TABLE 2 - JAMMA Connector

WIRE COLOR	SOLDER SIDE	PIN#	PIN#	PARTS SIDE	WIRE COLOR
BK	GROUND	A1	B1	GROUND	BK
BK	GROUND	A2	B2	GROUND	BK
RD	+5 VOLTS	A3	B3	+5 VOLTS	RD
RD	+5 VOLTS	A4	B4	+5 VOLTS	RD
BL	-5 VOLTS	A5	B5	-5 VOLTS	BL
OR	+12 VOLTS	A6	B6	+12 VOLTS	OR
	BLOCKING KEY	A7	B7	BLOCKING KEY	
VI	COIN COUNTER 2	A8	B8	COIN COUNTER 1	SL
		A9	B9		
WH/BK	SPEAKER (-)	A10	B10	SPEAKER (+)	BK/WH
GN		A11	B11		
GR	VIDEO-GREEN	A12	B12	VIDEO-RED	RD
WH	VIDEO-SYNC	A13	B13	VIDEO-BLUE	BL
YL	SERVICE SW.	A14	B14	VIDEO GROUND	BK
		A15	B15	TEST SW.	* BK/GN
RD	COIN SWITCH 2	A16	B16	COIN SWITCH 1	GN
RD/WH	2P START	A17	B17	1P START	BN/WH
YL/WH	2P UP	A18	B18	1P UP	YL
GN/WH	2P DOWN	A19	B19	1P DOWN	GN
OR/WH	2P LEFT	A20	B20	1P LEFT	OR
RD/WH	2P RIGHT	A21	B21	1P RIGHT	RD
BL/WH	2P SHOOT	A22	B22	1P SHOOT	BL
VI/WH	2P JUMP	A23	B23	1P JUMP	VI
PK/WH	NOT USED	A24	B24	NOT USED	PK
		A25	B25		
		A26	B26		
BK	GROUND	A27	B27	GROUND	BK
BK	GROUND	A28	B28	GROUND	BK

HIPPODROME™ UPRIGHT GAME & CONVERSION KIT

3. C. STANDARD CONNECTION DIAGRAMS

FIGURE 2 - Coin Counters & Coin Switches





FIGURE 3 - Coin Counter/Coin Switch Circuit




HIPPODROME™

Schematic Diagrams

DE 0318 - PROGRAM BOARD (17 Sheets)

DE 0297 - MAIN BOARD (17 Sheets)








圖號	DE 0318-3
圖名	PCB 1/17
日期	
設計	


圖號	DE 0318-3
圖名	PCB 1/17
日期	
設計	
校對	
審核	
材料	

1/17

圖號: 任務名稱




日期: 改訂個所: 零件號碼: 圖面號碼: 名稱: 任務名稱: 材料




開通番号	仕様・名称

図面番号	年月日	改訂箇所	仕様	部品	図面番号	名	仕様	材質



图样编号	任务, 名称


记录	号	担当	年月日	改	订	个	所	符号	部品	图面	番号	名	称	仕	様	材	質



图号	位号	名称

日期	年月日	改订	个数	所	行号	部品	图号	番号	名称	位号	材料


圖通番号 仕様名称




(1-6B) B0CQAD
 (1-8B) B0CQADLD
 (1-8B) *B0CQSEL0
 (1-8B) *B0CQSEL1
 (2-1B) B1CQAD

符号 年月日 改訂 箇所 符号 部品 図面番号 名称 仕様 材質

(2-3B) B1CQADLD
 (2-4B) *B1CQSEL0
 (2-4B) *B1CQSEL1





1	関連番号
2	仕様、名称


DE 0318-3 PCB 1/17
Page 21

(3-8A) *RST
(2-6A) 12M
(2-5A) *HLD0
(2-5A) *VLD0
(1-5A) 1P/2P
(12-4A) *HWR
(2-2A) HAB

(11-4A) *B2SEL
(12-6A) HDB


(13-5E) *XUS
(13-5E) *XLS

*VBLK (2-2E)
*NRAMRD (7-3E)
*NRAMWRL (7-3E)
*NRAMWRU (7-3E)
*HCLK (9-6E)
*B2CGADLB (10-4E)
*B2CGSELD (10-5E)
*B2CGSELD (10-4E)




1. 日期
 2. 设计
 3. 审核
 4. 批准
 5. 日期
 6. 设计
 7. 审核
 8. 批准
 9. 日期
 10. 设计
 11. 审核
 12. 批准
 13. 日期
 14. 设计
 15. 审核
 16. 批准
 17. 日期
 18. 设计
 19. 审核
 20. 批准

関連番号	仕様、名称
------	-------




12号	年月日	改訂箇所	符号	部品	図面番号	名	仕様	材質
-----	-----	------	----	----	------	---	----	----




11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100

記事

記号	担当	年月日	改訂箇所	符号	部品	図面番号	名称	仕様	材質
							PC-5		




記号担当	年月日	改訂箇所	符号	部品	図面番号	名	仕様	材質	頁
									5




関連番号	仕様, 名称

開通番号	
仕様名称	



記号	
担当	
年月日	
改訂箇所	
符号	
部品	
図面番号	
名称	
仕様	
材質	
備考	




图源编号	
任务名称	

记号	
担当	
年月日	
改订箇所	
符号	
部品	
图面番号	
名	
称	
仕様	
材質	
寸法	

第3角法


記号	担当	年月日	改訂	個	所	符号	部品	図面番号	名称	仕様
承継	野野	後園	藤田	長田	長田	長田	長田	長田	HFT-E1 回路図	LK-10060-1
50.5.5	50.5.5	50.5.5	50.5.5	50.5.5	50.5.5	50.5.5	50.5.5	50.5.5		



関連番号
仕様、名称

1
2
3
4
5
6
7
8
9

記号



材料	記号	年月日	改訂	個所	符号	部品	図面番号	名称	仕様
飛田	0297-3	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1
後田	02.07.06	02.07.06	改訂	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1	HT-E1

第3角法

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9


1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9

1
2
3
4
5
6
7
8
9




記 号

記号	担当	年月日	改訂	個所	符号	部品	図面番号	名称	仕様	材
12.5.76	菅野	62.5.76	改訂	長田	62.5.1	公差		HFT-E1回路図		
62.5.76	菅野	62.5.76	改訂	長田	62.2.10	公差		LK-10060-1		
62.5.76	菅野	62.5.76	改訂	長田	62.2.10	公差				

第3角法

12.5.76

関連番号	仕様、名称
------	-------



注1) HX58C65P-30 使用時は JPI の 3-4 を接続 (64K EEPROM 時)
 * MSM 2816A 又は X1com 2816A 使用時は JPI 1-2 を接続 (16K EEPROM 時)



記事

記号	担当	年月日	改訂	個	所	符号	部品	図面番号	名称	仕様
材料										
承認	担当	年月日	承認	年月日	担当	符号	部品	図面番号	名称	仕様
星野	長田	12.5.6	西川	12.4.7	長田	12.8.1	R度		HFT-E1 回路図	LK-10060-1
検印	検印	12.5.6	西川	12.4.7	長田	12.8.1	R度			

第3角法

回路図

1	関連番号
2	仕様名称




記事
 Back LSI用TRATRAMにTIM201B(10A11A)を4個取り入れ、7464を2個取り入れ、追加変更 62.12.19 版本

第3角法

記号	材料	担当	年月日	改訂	個所	符号	部品	図面番号	名称	仕様
62.12.19	7464	星野	62.12.19	1	回路	10A	7464	10A	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	11A	7464	11A	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	12A	7464	12A	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	13A	7464	13A	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	10B	LS273	10B	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	11B	LS273	11B	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	12B	LS273	12B	HFT-E1 回路図	
62.12.19	7464	星野	62.12.19	1	回路	13B	LS273	13B	HFT-E1 回路図	

回路図 10060-1

関連番号	
仕様、名称	




注) MB7116はICソケット使用のこと。

記事

記号	担当者	年月日	改訂	個所	符号	部品	図面番号	名称	仕様
承認	担当		訂	所				名称	
承認	年月日		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	
承認	担当者		訂	所				名称	

第3角法

開通番号	仕様名称
------	------




DE 0297-3 PCB 1/17
Page 39

記事

記号	担当	年月日	改訂	個所	符号	部品	図面番号	名称
12.5.8	坂田	22.5.8	改訂	坂田	LS	LS	LS	HFT-31回路図
12.5.8	坂田	22.5.8	改訂	坂田	LS	LS	LS	LK-10060-1

第3角法

三菱電機株式会社



記事
※注意 指示付きPinは必ずNCにしてください。

第3角法

記号	担当	年月日	改訂	箇所	符号	部品	図面番号	名称	仕様
材質			処理					(GE-0295) MKC-06 FLA	HFT-E1 回線図
承認	検閲		承認	担当	単位	mm	図番	LK-10060-1	

記事

- (1-5A) CPUDB
- (1-1A) R/W
- (1-1A) CPUAB
- (1-1A) B&C
- (11-3A) MCOL
- (7-5A) B.I.C



RAIS

J,Kx8

- (1-4A) *UDS
- (3-3A) *PSEL #
- (1-4A) *LDS
- (3-3A) *PSEL I
- (1-1A) *CLR
- (1-1A) *UWR

材料	記号	担当	年月日	改訂	個所	符号	部品	公差	図面番号	名称
樹脂	樹脂	長田	62.2.10	増設	増設	増設	増設	増設	増設	HFT-E1 回路図
銅	銅	長田	62.2.10	増設	増設	増設	増設	増設	増設	LK-10060-1

第3角法

リテラ

1) PRISEL

注) MB7122 はICソケット使用のこと。

関連番号

仕様名称

RC0 (13-1E)

QC0 (13-4E)

BC0 (13-6E)

1

2

3

4

5


6

7

8


9

回路番号	仕様名称
------	------



記号	担当者	年月日	改訂	個所	番号	部品	図面番号	名称	仕様
材料									
12.5.76	長田	82.5.76		西川	63.5.1	HTT-E1	回路図	HTT-E1	回路図
	長田	82.2.10		長田	63.5.1	HTT-E1	回路図	HTT-E1	回路図
	長田	82.2.10		長田	63.5.1	HTT-E1	回路図	HTT-E1	回路図

第3角法



1
2
3
4
5
6
7
8
9

10
11
12
13
14
15


16
17
18
19
20
21
22
23
24
25

26
27
28
29
30
31
32
33
34
35

36
37
38
39
40
41
42
43
44
45

46
47
48
49
50
51
52
53
54
55

56
57
58
59
60
61
62
63
64
65



注) 6502Aは、CN2の近くに配置すること。



記事

記号	担当者	年月日	改訂	個所	番号	部品	図面番号	名称	仕様
材料	望野	62.5.6	西川	長田	17	LS	374	HFT-E1回路図	LK-10060-1
承認	渡辺	62.5.8	西川	長田	17	LS	374		
承認	西川	62.4.7	長田	長田	17	LS	374		
承認	長田	62.2.10	長田	長田	17	LS	374		
承認	長田	62.2.10	長田	長田	17	LS	374		

第3角法

データ

記号



※破線内は
グランドプレーン
にすること。
アンプのGNDは
エレクトロニクスのPHT
接続すること

第3角法

記号	材料	年月日	改訂	個所	符号	部品	図面番号	名称	仕様
12.5.6	望野	18.2.6	1	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	2	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	3	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	4	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	5	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	6	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	7	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	8	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	9	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1
12.5.6	望野	18.2.6	10	藤本	1	HT-E1	回路図	HT-E1 回路図	LK-10060-1

HIPPODROME™
UPRIGHT GAME & CONVERSION KIT

5. 0. CUSTOMER RESPONSE

This HIPPODROME™ Installation and Service Manual includes schematic diagrams, and should answer almost all of the technical questions that you may have. Should you require additional, or more detailed information, you should contact the DATA EAST distributor from whom you have purchased the game. His highly qualified staff will, most likely, be able to answer your questions, or give you the proper direction. If, after consulting with your distributor, you still require additional assistance, you may contact the DATA EAST service department at (408) 286-7080, between the hours of 8:00 AM and 5:00 PM Pacific time. When contacting your distributor, or when contacting DATA EAST, please be prepared to provide the serial numbers for the game pcb (printed on the original product seal), the "AAMA PROTECT" sticker, and the game cabinet.

DATA EAST welcomes all constructive feedback, both negative and positive. We would be pleased if you would write us directly with you comments concerning our products and services. Our address is:

Data East USA, Inc.
470 Needles Drive
San Jose, CA 95112
Attn: Customer Service Dept.

Be sure to indicate whether you wish to have your name added to our mailing list for service bulletins and product updates. The form below is provided for your convenience

HIPPODROME™ CUSTOMER RESPONSE

COMPANY NAME: _____

ADDRESS: _____

CITY: _____ STATE: _____ ZIP: _____

TELEPHONE: _____

YOUR NAME: _____ TITLE: _____

GAME CABINET SERIAL NUMBER _____

PCB SERIAL NUMBER _____ AAMA # _____

(from Original Product Seal)

ADD YOUR COMPANY TO OUR DIRECT MAIL LIST? (circle one) YES NO

COMMENTS: _____

WARRANTY INFORMATION

Data East USA, Inc., ("Seller"), warrants only to the original purchaser ("Buyer"), of its products that the items listed below are free from defects in material and workmanship under normal use and service for the period specified:

GAME LOGIC PRINTED CIRCUIT BOARD(S)

90 DAYS

No other parts of the Seller's products are warranted.

Warranty periods are effective from date of initial shipment from Seller to Buyer. Seller's sole liability shall be, at its option, to repair or replace products which are returned to Seller during the warranty periods specified, provided:

1. Seller is notified promptly upon discovery by buyer that stated products are defective.
2. Such products are properly packaged and then returned freight pre-paid, to a place specified by Seller.

This warranty does not apply to products damaged during shipment and/or due to improper handling, or due to improper installation or usage, or alteration. In no event shall Seller be liable for any anticipated profits, loss of profits, loss of use, accidental or consequential damages, or any other losses incurred by the customer in connection with the purchase of a Data East USA, Inc., product.

WARRANTY DISCLAIMER

EXCEPT AS SPECIFICALLY PROVIDED IN A WRITTEN CONTRACT BETWEEN SELLER AND BUYER, THERE ARE NO OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING ANY IMPLIED WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

